	INSTALL THE FOLLOWING MITSUBISHI MULTI ZONE MR SLIM SYSTEM	
1	MXZ8 MULTI-ZONE HEAT PUMP	
3	MSZGE06 WALL MOUNT AIR HANDLER WITH WIRELESS REMOTE CONTROL	
2	MSZGE09 WALL MOUNT AIR HANDLER WITH WIRELESS REMOTE CONTROL	
1	MSZGE18 WALL MOUNT AIR HANDLER WITH WIRELESS REMOTE CONTROL	
1	SEZKD12 MITSUBISHI DUCTED INDOOR UNIT	
1	PAC-AKA51 5 PORT BRANCH BOW	
1	PAC-AKA51 3 PORT BRANCH BOW	
	PROPOSED INSTALLATION PRICE INCLUDING TUBING TO AIR HANDLERS, CONDENSOR BRANCH BOX,	
	FLARE CONNECTIONS, SUPPLY & RETURN AIR DUCTWORK, REGISTERS AND DIFFUSERS FOR BASEMENT,	
	MATERIALS, LABOR, AND TAX.	
	EXCLUDES ELECTRICAL, PERMITS AND CONDENSATE	<u>\$19,500</u>
	RADIANT FLOOR-BASEMENT	
	PROVIDE AND INSTALL RADIANT FLOOR HEATING SYSTEM FOR THE BASEMENT. INCLUDES 96% EFFICIENT	
	BOILER, PUMPS, TUBING, MANIFOLDS, INTAKE AND EXHAUST PVC AND CONTROLS	
	EXCLUDES GAS PIPING, ELECTRICAL, UNDERSLAB INSULATION	<u>\$15,995</u>
	RADIANT FLOOR-MAIN LEVEL	
	STAPLE TUBING UNDER SUBFLOOR BETWEEN TRUSSES. INCLUDES 3 ZONES OF RADIANT FLOOR HEAT WITH	
	CONTROLS.	
	EXCLUDES FOIL-FACED BATTS INSULATION WHICH IS REQUIRED BETWEEN THE TRUSSES	<u>\$17,250</u>