

**Zehnder
Comfosystems**

540 Portsmouth Ave.
Greenland NH 03840



Quote number: **4-0220-10.14**
Project: **Sheehy Residence**
City: **Whitefield**
State: **ME**
Created by: **Norbert Wesely**
Date: **4-Apr-13**

Customer: **T.A. Greenleave Fine Woodworking & Home Building,**
To attention of: **Tom Greenleave**
Phone contact: **207.542.2926**

Remarks: Boost switches are included for each full bathroom.
Amount of ComfoPipe (for intake/exhaust ducting) and ComfoTube (for distribution ducting) have been estimated as carefully as possible. Confirm layouts prior to ordering to ensure sufficient materials for installation.
Note that this quote does not include shipping which can vary widely dependent upon several factors and will have to be calculated when ordering. Local pick-up available at the warehouse in Haverhill, MA.

Calculation of the required air flow rates

Floor	Room	Area [ft²]	Height [ft]	Volume [ft³]
First Floor	Office			
	Living Room			
	M Bed Room			
	M Bath			
	Kitchen			
	Powder room	1,650	8.2	13,530
Total		1,650		13,530

Air exchange rate per hour **0.32**

Air volume [cfm]	
Supply Air	Exhaust Air
24	
24	
24	
	24
	36
	12
72	72

**Zehnder
Comfosystems**

540 Portsmouth Ave.
Greenland NH 03840



Quote number: **4-0220-10.14**
Project: **Sheehy Residence**
City: **Whitefield**
State: **ME**
Created by: **Norbert Wesely**
Date: **4-Apr-13**

Comfosystems quotation

Article No.	Description	Quantity	List price piece	List price total
9281	ComfoAir 200 Ventilation device HRV VV Left with Pre-Heater	1	\$2,395	\$2,395
9362	Waterless P-Trap	1	\$59	\$59
9257	ComfoSense Controller with Mounting Box	1	\$199	\$199
9238	Remote-controlled unit Ease	1	\$99	\$99
9290	ComfoPipe 150/6" x 39"	7	\$45	\$315
9294	ComfoPipe 150/6" x 90 Deg	7	\$29	\$203
9296	ComfoPipe 150/6" Sleeve	2	\$20	\$40
9446	Roflex 150 Gasket PR w/tape	1	\$42	\$42
9410	Exterior Wall Grill 150/6"	2	\$109	\$218
9325	ComfoWell Mounting kit CA 200 CW-K 320	1	\$169	\$169
9319	ComfoWell Silencer CW-S 320	2	\$249	\$498
9329	ComfoWell Manifold CW-M 320 6 ports 75 (3")	2	\$89	\$178
9272	ComfoTube 75 ventilation tube 3" x 162.5 Ft.	3	\$299	\$897
9274	ComfoTube 75 O-Ring (Each)	30	\$2	\$60
9277	ComfoTube 90 cap (Each)	1	\$6	\$6
9442	TVA 75-3 Port diffuser box	1	\$109	\$109
9441	Return diffuser STB - 2 125 (5")	1	\$45	\$45
9308	ComfoTube diffuser box TVA 75	5	\$69	\$345
9310	Return diffuser STB - 1 125 (5")	2	\$28	\$56
9443	Diffuser cover round Venezia White	3	\$59	\$177
9352	Filter 125 mm (Each) For return diffusers	2	\$5	\$10
9282	Filter G4 (Each) (MERV 7/8) ComfoAir 200	2	\$22	\$44

TOTAL	\$6,164
Contractor Discount	20%
EQUIPMENT TOTAL	\$4,931.20
Commissioning Fee	\$500
PROJECT TOTAL	\$5,431.20

Conditions:

This quotation is applicable solely for the materials listed and in the quantities shown and is based upon the system design as understood at the time of the quotation. Changes to the system design, deviations in the actual construction or in the expected installation process may result in additional material requirements which are not included in this quotation.

This quotation is valid for the attached floorplan only and the layout must be confirmed by the purchaser prior to ordering to insure sufficient materials for installation.

Terms:

Quotation valid for 90 days from date above.

Shipping: FOB Ward Hill, MA or Port of Entry. Zehnder will select carrier unless otherwise requested by customer.

Payment terms: Credit Card unless otherwise agreed upon