

BRICK LINTEL SCHEDULE

SPAN	END SUPPORT	STEEL ANGLE
≤6'	4"	L3x4x1/4
8'	6"	L4x4x1/4
10'	6"	L4x4x1/2
12'*	8"	L6x4x1/2
16'*	8"	L6x4x1/2
18'*	8"	L6x4x1/2

- PRIME ALL LINTELS WITH TNE MEC PRIMER BEFORE INSTALLATION.
- FLASHING MUST FULLY COVER STEEL ANGLE.
- SHORE MID-SPAN FOR SEVEN DAYS.
- DATA SHOULD BE VERIFIED BY ENGINEER.
- * ATTACH LINTEL TO HEADER WITH 1/2"x4" GALVANIZED LAG BOLTS @ 16" O.C.
- * SHORE SPAN 3X FOR SEVEN DAYS
- * (1) 3/16" DIA. GALV. WIRE 1ST 2 COURSES.

