



5-1/2" THERMACAL1 VENTILATED ROOF INSULATION
PANELS W/ 5/8" THK SHEATHING AS MANUFACTURED BY
GAF CORNELL PERFORMANCE BUILDING PRODUCTS WITH
9" SIPTP FASTNERS @ 16" O.C. VERITCAL AND
HORIZONTAL, PROVIDE MINIMUM 1.5" THREAD
EMBEDMENT

5/8" THK ZIP SYSTEM ROOF SHEATHING

SDWC 15600 (6") LONG SCREW

2 X 10 LEDGER BOARD, PROVIDE 1/2" THRU BOLT
@ 16" O.C. AND 1/2' LAG BOLT INTO EVERY
RAFTER, OVERHANG TO BE BENCH BUILT IN 8'-0"
SECTIONS AND ATTACHED TO STRUCTURE AFTER
ENVELOPE IS COMPLETE

EXTEND ICE AND WATER SHIELD
FROM ROOF TO MIDWAY OF
FASCIA BOARD BEHIND GUTTER.

NEW .032 ALUMINUM GUTTER
COLOR AS SELECTED B.O.