WALL TO ROOF DETAIL

$\frac{7}{16}$" ZIP

Prosoco FastFlash
or
ZIP Liquid Flash?
(installed in continuous line
around all four sides)

1 $\frac{7}{16}$" ZIP R6-SHEATHING
BETWEEN RAFTERS

ROOFING
1. 30 LBS FELT.

2. 36" WIDE STRIP OF GAF STORMGUARD /
CERTAINTEED WINTERGUARD PLACED IN
VALLEYS AND ON ROOF EDGE.

3. LIFETIME RATED ASPHALT SHINGLES
(CERTAINTEED LANDMARK OR GAF TIMBERLINE
HD OR BETTER).

2x4

Drip Edge

2x4   2x6

ENERGY
HEEL
TRUSS

$\frac{3}{4}$ x 7 $\frac{1}{4}$
(Hardietrim)

$\frac{3}{4}$ x 3 $\frac{1}{2}$
(Hardietrim)

$\frac{1}{4}$" x 16"
Vented
(Hardie)

Brick

1'-4"

AT LEAST 6" OF
GREENGUARD GOLD CERTIFED
OPEN CELL SPRAY FOAM

Heckmann 75TCMNA
Barrel Screw
(pre-drill $\frac{3}{8}$" hole thru ZIP prior to
installing)

2x6

Heckmann
75T3HTriangle Wire Tie
(every 16" horizontally
and 24" vertically)

2x4

$\frac{7}{16}$"
OSB

1 $\frac{7}{16}$" ZIP R6-SHEATHING
BETWEEN RAFTERS AND

2x4

$\frac{5}{8}$"
Sheetrock

Not Shown:
1. Stainless Steel weep vents (every 2-3
bricks, not to exceed 24") on bottom of wall
and top of wall

Other Notes:
1. Use Heckmann Building Products Barrell
Screw P/N 75TCMNA (1.5" long) and Triangle
Wire Tie (Pos-I-Tie System) P/N 75T3H ($\frac{3}{16}$" x
3" long, hot-dipped galvanized) to secure
brick/stone to wall panel

3'

6.00