

			_
ACTIVITY	TAX	AMOUNT	
M.B. Eye Electrical is pleased to offer Mr. Marty Nichol a quote for a Solar Photovoltaic System as requested			
Services Provide and install 11.2 kW roof-mounted Solar PV system - 28 x 400W LG solar panels - 28 x Enphase Microinverters and trunk cable - Spider roof racking with flashing, footings, and all hardware All footings and flashing will be installed by roofing contractor	HST PEI 15%	30,352.00	

- Enphase Envoy for online monitoring
   All electrical wiring, including Net Meter install, included
   All permits and electrical inspections included
- Estimated annual energy production: 13,440kWh
- 50% ordering deposit required

Additional information required for Solar Rebate form:
- Orientation: 158 degrees
- Roof Slope: 8/12 = 33.6 degrees
- Annual Shading Factor: -0.1%
- Roof Condition: 5 years

- First year energy savings: 13,440kWh @ 0.1437/kWh = \$1931.33

**SUBTOTAL** 30,352.00 **GST/HST @ 15%** 4,552.80

\$34,904.80 TOTAL

Accepted By **Accepted Date**