



- 1/2" Structural Sheathing - 5 Ply CDX - Taped Seams (Top.)
- Housewrap
- 2" Polyiso Rigid Foam Insulation - 2 1/2" Roofing Nails - Taped Seams
- 1x Strapping Beyond
- 5/8" Rough-Sawn Plywood Siding - No Groove
- 1x2 Trim Board Beyond - 1 1/2" Nails
- Subfloor
- Polyiso Rigid Foam & Spray Foam at Rim Joist
- Threaded Rod Connects to J-Bolt Anchor in Concrete Stem Wall
- L.S. Rim Joist
- Sill Plate
- Flashing Tape
- Cor-A-Vent SV-3 Siding Vent
- 2x PT Blocking
- 1x Cedar Trim
- Concrete Stem Wall
- Polyiso Rigid Foam

1
A7.4
Rim Joist Detail
3/4" = 1'-0"

Miles TeSelle
3118 NE 70th Ave
Portland, OR 97215
503.956.3416

1
3/20/25 Added Beams, Added Deck, Revised Trusses & Roof Overhang, Revised Cladding, Revised Insulation, Added Details.

TeSelle-Hood Cabin

Page
A7.4